

ADDENDA FOR TENDER NO: 8/2/RNM0415 – RENOVATIONS OF THE MAIN OFFICE



03 April 2023

ALL BIDDERS

Dear Sir/Madam

RENOVATIONS OF THE MAIN OFFICE - TENDER NO: 8/2/RNM0415 – ADDENDUM NO.1

With reference to the above tender, kindly receive the Addendum No. 01 due to a correction of A9. Details of Key Personnel and change in the Bills of Quantities.

This Addendum forms an integral part of the Tender Notice and Invitations to Tender, Tender Data, Contract Data, Specifications (including the Project specifications), Bill of Quantities, Returnable Documents, Form of Offer and Acceptance to be completed for this Contract, and takes precedence. Notwithstanding anything said during the tender period or the clarification meeting, only the additional information or variations contained in this Addendum and subsequent Addenda, if any, will be legally binding.

Changes to be done as follows:

- The page below should **replace** Page 45 – A9. DETAILS OF KEY PERSONNEL - reflected as page 39 on the tender document.
- The page below should **replace** Page 103 reflected as page 97 of the Bills of Quantities on the tender document.

Regards,

Ms. Thabsile Ngcobo
For Ray Nkonyeni Municipality

Acknowledgement of receipt:
TO BE FORWARDED TO Thabsile.Ngcobo@rnm.gov.za

ATTENTION: Ms. Thabsile Ngcobo
ADDENDUM NO.1: FOR TENDER NO: 8/2/RNM0415
We:

Company: _____ **Date:** _____

Name & Surname: _____ **Signature:** _____

do hereby acknowledge receipt of ADDENDUM No.1

RAY NKONYENI MUNICIPALITY

RAY NKONYENI MUNICIPALITY
NOTICE NO: 012 OF 2023
TENDER NO: 8/2/RNM0415

DETAILS OF KEY PERSONNEL

Tenderers shall set out in the Schedule hereunder details of the experience of the Site Agent and Site Foreman in work of a similar nature to that for which this Tender is submitted.

Failure to complete this Schedule may result in the Tender not being considered.

SITE AGENT				
NAME:			NQF LEVEL:	
Contract and Client	Nature Of Work	Position Held	Value Of Work	Year Completed

SITE FOREMAN				
NAME:			NQF LEVEL:	
Contract and Client	Nature Of Work	Position Held	Value Of Work	Year Completed

Item No		Quantity	Rate	Amount
	<u>Soudal polyurethane sealer on all outlets</u>			
4	Around pipes and into outlets, etc	No	10	
	<u>WATERPROOFING TO TILE ROOF</u>			
	<u>Strip away existing roof tiles across certain areas of flashing to be waterproofed, remove redundant waterproofing system and check all roof timbers and replace with SABS treated timber 38 x 38 battens where necessary</u>			
5	On identified areas	P Sum	1	100000,00
6	Allow for profit and attendance	%	10	
	<u>SABS Roof waterproofing system across certain areas with a 100mm overlap; install new aluminium valley irons if necessary; re-tile using existing roof tiles; replace and reseal ridging using W119 cement sealer and bonding liquid; counter-flash with three coats where necessary with W112 Elastomeric Acrylic Compound/membrane and seal ridging with Wilbond acrylic sealer</u>			
7	On identified areas	m ²	600	
	Carried to Collection			
	Bill No 2 Section 2 Waterproofing			